


Project Profile



Project Title	Odsal Stadium Bradford
Client	Bradford Bulls Rugby League
Project Value	£3.2m
Contract Conditions	Standard ACE appointment with conventional tender (JCT)
Duration	8 months
BSCP Services	Full design, detailing, site and contamination assesment

Description

The new Hospitality Stand for Bradford Bulls was constructed at the end of the Odsal Stadium on the site of the old Speedway Pits. The site was steeply sloping and terraced and comprised 15—20 meters of fill overlying the original valley bottom. At the bottom of the valley the original drainage culverts still existed and these gave rise to particular problems with foundations.. The whole of the hospitality complex sits on only 18 piles which penetrate the fill to the underlying natural strata.. The superstructure is an innovative tree column structure which was devised to transfer the majority of superstructure loads to relatively few supports.. These in turn are supported by only 4 piles at the front of the building..The building is elevated above pitch level to fit in with the natural contours giving a ground floor to the new stand approximately 5m above pitch level and the first floor approximately 8.5m above pitch level



BSCP
Part of the
gha livigunn group

Cheadle

0161 4914 600

Frodsham

01928 734777

Leeds

0113 261 0022

www.ghalivigunn.com