

Project Profile



Project Title	O2 Arena Ice Pad
Client	Steyson Granolithic
Contract Value	£360K
GHA Livigunn Services	Flooring Contractor

Description

The design of a 60m x 30m ice pad using a highly modified concrete mix to minimize the risk of shrinkage cracking occurring without the need for shrinkage stress relief joints. Steel fabric reinforcement was used to aid control cracking and support embedded cooling pipes positioned centrally in the floors depth.

Cheadle

0161 4914 600

Frodsham

01928 734777

Leeds

0113 261 0022

www.ghalivigunn.com