

## Project Profile



Project Title	Park Royal Hotel—New Bedroom Block and Leisure Centre
Client	Midmint
Project Value	£9m
Duration	105 weeks
Duration	56 weeks
GHA Livigunn Services	Civil and Structural Engineering

**Description**

Construction work for two new 120 room bedroom blocks and leisure centre were located immediately adjacent to the existing 18th century entrance to the hotel on an area of existing car parking. To maintain clear access and to minimise impact the works were erected in phases.

The two bedroom blocks were designed in traditional load bearing masonry with basements founded on mudstone, whilst the leisure complex requiring wider clear spans was designed as a braced steel frame. Due to poor ground conditions in this area the structure was piled.

**Cheadle**

**Frodsham**

**Leeds**

0161 4914 600

01928 734777

0113 261 0022